



Office
7 Arnett Place
Wetherill Park NSW 2164
Ph 1800 281 303
Fax 1300 795 202
ABN 85 516 019 087



The Escort® Permanent Handrail System provides safe working areas for all maintenance personnel without the need for the use of cumbersome safety harnesses and the extra training required. The Escort® Permanent handrail system eliminates the hazard rather than minimizing it.

Features

- ✓ Prefabricated modular componentry ensures easy on site assembly – no welding required
- ✓ Lightweight, high strength aluminium construction
- ✓ Designed and tested to 60kg horizontal loading
- ✓ Unique swivelling elbow design ensures easy and tidy installation
- ✓ Low maintenance and neat appearance
- ✓ Suits many varied applications and locations

Specification Summary

Supply and install the proprietary Escort® Handrail System as per manufacturer, Monkey Toe Systems Ltd recommendations. Escort® Handrail System to be of high grade aluminium components. When used with the Monkey Toe® roof access system fixings must be the Monkey Toe® Roofing clips. When used with the Éclat® Walkway system fixings are to be 5mm bulb-tite rivets. The handrail must be 1100mm from the access level. Max spacing's between the kick and knee rail are to be no more than 460mm. Kick rail to be no more than 150mm from access level.

System Applications

- ✓ Ideally suited as a permanent Handrail system to eliminate the hazards.
- ✓ Roof top mounted handrails
- ✓ Plant Platform handrails

Technical Data

Material

All componentry and accessories manufactured from high grade structural aluminium with options for powder coating.

Fixings

Monkey Toe fixings 14 Gauge teks and/or accessories

General Fixing 5mm bulb-tite rivets

Compliance

Support structure integrity, suitability and fixing method to be assessed and determined by a competent person prior to installation

Inspection and Maintenance

Visual inspection for any damage or loose fixings must be done periodically and prior to use.

No certified maintenance is required. Basic wear and tear preventative maintenance is recommended

Important Note

Failure to supply and/or install proprietary product in accordance with above specification and installation/usage guidelines voids complete system certification and/or warranty.



*Monkey Toe Walkway with Handrails
Both Sides*



Éclat Walkway with Handrails Both Sides